

IMPLEMENTATION ROADMAP

Pilot Phase (0–3 Months)

- Install a small pilot system (21 kW solar + Battery 300 kw)
- Integrate VFD, MPPT, BMS, IoT monitoring on one pump line
- Test performance: solar yield, battery backup, dust impact, pumping stability
- Finalize optimized design for full deployment.

Full Deployment (3–9 Months)

- Install ~100 kW solar + ~320 kWh LiFePO₄ battery.
- Integrate grid + diesel (4h + 2h logic) with automatic switching.
- Deploy AI-based tracker, automatic dust cleaning, and full EMS.
- Achieve 24/7 hybrid dewatering with major diesel reduction.

Optimization & Scaling (9– 18 Months)

- Add AI optimization, predictive maintenance, seasonal tuning.
- Improve efficiency and reduce diesel to minimum.
- Prepare a replicable model for other HCL mining sites.

METHODOLOGY & PROCESSES

Cost-efficient model
enabling vendor-
managed installation,
operation, and
maintenance without
upfront investment

OPEX-Based Design

End-to-end IoT
connectivity enabling
real-time sensor
communication, device
control, and data
synchronization


IoT Integration

On-site validation of
pump performance,
power output, sensor
accuracy, and safety
thresholds before
activation

System Testing & Calibration

Cloud-based analysis of
flow patterns, energy
savings, and pump
efficiency for
continuous
improvement

Performance Analytics



Resource Mapping

Assessment of water
flow, pump head, land
availability, solar
irradiance, and PV sizing
for optimized system
planning

Modular Installation

Scalable deployment of
solar panels, pumps,
sensors, and control
units with plug-and-play
field integration

Automation & Monitoring

Live dashboard insights
with automated alerts,
pump control logic, and
AI-driven predictive
maintenance

Hybrid Continuity Planning

Backup alignment with
grid/diesel systems to
guarantee
uninterrupted pumping
during low-sun
conditions